

# Standard Features:

- Fiberglass Reinforced Polyester (FRP), NEMA Type 4X enclosure
- PreVent<sup>™</sup> breather vent
- Conformal coated circuit board
- Removable load cell connectors
- Section and individual cell trim capability
- Number of cells: 2, 4, 6 or 8 single load cells (even number only)
- Expansion port


# Part Number/Price


Part#	Description	Price	
91782	JB8SP signal trim eight-channel with expansion	\$425.00	
173807	JB8SP signal trim eight-channel with expansion, FM approved	\$425.00	
89889	Board only	\$365.00	
172415	Board only, FM approved	\$365.00	
165273	Enclosure only (does not include cord grip and filter)	\$135.00	

Note: Do not mix junction box models or use other brands of junction boxes with Rice Lake junction boxes. There is a risk of system instability.

## **Options/Accessories**

Part#	Description	Price
92734	Coupling, 1/2 in NPT cord grip to 3/4 in NPT conduit fitting	\$25.00
92735	Coupling, 3/8 in NPT cord grip to 3/4 in NPT conduit fitting	\$25.00





# Specifications:

#### Cable Fittings:

(9) 3/8 in NPT 0.157 in-0.314 in (2) 1/2 in NPT 0.272 in-0.472 in (1) PreVent breather unit

Individual cell trim, range

### Enclosure:

Molded FRP NEMA Type 4X enclosure with overlapping solid cover, stainless steel screws

#### Connectors: Pluggable screw type, 12-28 AWG



**Approvals** 

FM

APPROVED

100K ohm, 25 turn cermet Circuit Board:

**Potentiometers:** 

**Trimming:** 

5.7 in x 7.2 in with conformal coating

Warranty: One-year warranty

## **Applications:**

• Truck, livestock and railroad scales

604

RICE LAKE